



State of Utah

GARY R. HERBERT  
*Governor*

SPENCER J. COX  
*Lieutenant Governor*

DEPARTMENT OF TRANSPORTATION

CARLOS M. BRACERAS, P.E.  
*Executive Director*

SHANE M. MARSHALL, P.E.  
*Deputy Director*

April 28, 2016

TO ALL BIDDERS CONCERNED:

SUBJECT:

F-0109(4)0 / Pin 012284  
SR-109; SR-126 to US-89  
Addendum Number: 1

To Whom It May Concern:

We are submitting the following changes to the subject project.

1. Special Provision 00555M "Prosecution and Progress" has been revised.

Please consider these revisions before submitting your bid.

**\*\*\* ADDENDUM IS AVAILABLE AND MAY BE DOWNLOADED FROM THE UDOT WEBSITE AT  
<http://eprpw.dot.utah.gov>**

**RECEIPT OF THIS ADDENDUM MUST BE ACKNOWLEDGED WHEN YOU SUBMIT YOUR BID.  
YOUR BID WILL BE DECLARED NON-RESPONSIVE IF YOU DO NOT ACKNOWLEDGE THIS  
ADDENDUM.**

Sincerely,

A handwritten signature in blue ink, appearing to read "B. Slater".

BRETT SLATER  
Project Manager

Attach:

---

April 27, 2016

**SPECIAL PROVISION**

**PROJECT # F-0109(4)0  
PIN # 12284**

**SECTION 00555M**

**PROSECUTION AND PROGRESS**

**Add the following to Part 1, Article 1.11:**

**1.11 LIMITATIONS OF OPERATIONS**

- A. Minimize interference with traffic during performance of the work.
- B. Sunday and Holiday Work
  - 1. Do not perform any work without written approval except for repairing or servicing equipment, protecting work, maintaining or curing concrete, and maintaining traffic during the following holiday weekends: Memorial Day, Independence Day, and Labor Day.
    - a. Holiday weekends are defined as the Saturday and Sunday prior to a holiday if it falls on a Monday, and Saturday and Sunday after if the holiday falls on a Friday.
- C. Working Hours and Construction Access
  - 1. Night Work
    - a. Provide notice five calendar days before starting night work.
    - b. Provide adequate lighting for performing satisfactory inspection and construction operations.
    - c. Control noise and vibration according to Section 01355.
- D. Traffic is permitted on rotomilled surfaces for no more than 48 hours. Provide adequate signing to notify drivers and sweeping to prevent vehicle damage. Provide a smooth transition in and out of rotomilled areas.
- E. Conduct work to minimize lane closures. When lane closures are necessary, meet the following conditions:
  - 1. Do not delay any vehicle for more than fifteen minutes.
    - a. Adjust flagging/pilot car operations and closure lengths as needed to meet this requirement.
    - b. Adjustments may be needed in traffic control due to peak hours.

- F. No lane closures are allowed during the following times unless approved by the Engineer in writing:

ROUTE	DIRECTION	DAYS	TIME
SR-126 to 1350 East	EB, WB	Monday – Saturday	6:00 AM to 8:00PM
1350 East to US-89	EB,WB	Monday – Friday	6:00 AM to 8:00PM

Lane closures in violation to above times will have a disincentive of \$2,000 per violation assessed to the Contractor. When the violation exceeds 15 minutes, an additional \$1,000 will be assessed every 15 minutes until traffic is restored to the required number of lanes.

1. Maintain all left turn pockets at all signalized intersections between 6:00 AM and 10:00 PM.
  2. Maintain one lane in each direction at all time between SR-126 to 1350 East.
- G. Do not extend work zone beyond one mile at any given time during construction.
- H. Category II Holiday Work
1. Do not perform any work without written approval except for repairing or servicing equipment, protecting work, maintaining or curing concrete, and maintaining traffic control on Category II holidays as defined in Section 00570.
    - c. July 1<sup>st</sup>, 2016 12:00 pm to July 4<sup>th</sup>, 2016 11:59 pm (Independence Day)
    - d. July 22<sup>nd</sup>, 2016 12:00 pm to July 24<sup>th</sup>, 2016 11:59 pm (Pioneer Day)
    - e. Sept. 2<sup>nd</sup>, 2016 12:00 pm to Sept. 5<sup>th</sup>, 2016 11:59 pm (Labor day)
- I. Maintain access to properties
1. Notify all property owners/occupants 48 hours in advance of any partial closure.
- J. Prior to adjusting any manholes or valves, visually inspect the condition by pulling the lid off. If there is anything in need of repair, document the condition and notify the Engineer and utility owner.
- K. Provide at least three Variable Message Signs (VMS) 6 calendar days prior to beginning work and available for use during construction. Replace any partial or non-functioning VMS at no cost to the department. Messages must reflect current project conditions and properly advise motorists of construction activities and impacts. The cost of the VMS is to be included in the traffic control item. Coordinate the location and message with the Engineer and the Traffic Engineer. Relocate the VMS as directed by the Engineer and/or to accommodate traffic queuing at no

additional cost. Warning signs must precede the queuing traffic at all times and be close enough to the work zone to maintain relevance. Notify the public and businesses within the anticipated work zone, at least 72 hours prior to lane closures.

- L. Coordinate traffic control plans and construction activities with any adjacent active construction projects. Known projects include:
  - 2. Commercial Development for WinCo Foods. Owner / Developer Winco Foods, LLC 65 North Armstrong Place Boise, Idaho 83704 PH: (801) 672-2066:  
  
Teddy Owens, Superintendent, Engineered Structures Inc. 208-362-3404 (Office), 208-921-2542 (Mobile), [teddyowens@esiconstruction.com](mailto:teddyowens@esiconstruction.com)  
  
Dean Jones, EK Bailey, 801-430-1698
- M. Prior to July 1<sup>st</sup> no work to be performed between SR-126 and Fort Lane.
- N. Maintain School Flashing Beacon during school hours. Coordinate with Layton city for power connection.